


CITY OF JANESVILLE, JANESVILLE, WI DRAFT 99% Design, August 24, 2017



LOCATION MAP

SHEET LIST

- 1 TITLE SHEET & SHEET INDEX
- 2 GENERAL NOTES
- 2 CITE DI
- 4 DEMOLITION PLAN
- 5 PROPOSED CONDITIONS SHEET 1 OF 3
- 6 CONSTRUCTION CROSS SECTIONS
- 8 PROPOSED CONDITIONS SHEET 3 OF 3
- 9 TYPICAL DETAILS SHEET 1 OF 4
- 10 TYPICAL DETAILS SHEET 2 OF 4
- 11 TYPICAL DETAILS SHEET 3 OF 4
- 12 TYPICAL DETAILS SHEET 4 OF 4

			DF, CP, BL	BW	BW
			DRAWN	DESIGNED	CHECKED
			BW	8/24/17	15-04-13
			APPROVED	DATE	PROJECT
NO.	DATE	REVISION DESCRIPTION	ATTROVED	DAIL	THOSECT

LOCATION MAP - WISCONSIN

MONTEREY DAM REMOVAL CITY OF JANESVILLE JANESVILLE, WI

E RACINE ST

11

VICINITY MAP



Madison, WI 53703 608.441.0342 www.interfluve.com

TITLE SHEET & SHEET INDEX

SHEET

1 of **12**

Preliminary Blot for Construction

GENERAL PROJECT NOTES

- THE UNDERGROUND UTILITY INFORMATION, AS SHOWN HERE, IS BASED, IN PART, UPON INFORMATION FURNISHED BY UTILITY COMPANIES AND THE LOCAL MUNICIPALITY. WHILE THIS INFORMATION IS BELIEVED TO BE RELIABLE, IT'S ACCURACY AND COMPLETENESS CANNOT BE GUARANTEED OR CERTIFIED.
- PRIOR TO EXCAVATION CALL TOLL FREE, DIGGERS HOTLINE, 1-800-242-8511. COST OF REPLACEMENT OR REPAIR OF EXISTING UTILITIES DAMAGED AS A RESULT OF THE CONTRACTOR'S OPERATION SHALL BE THE
- ELEVATIONS SHOWN ON THIS PLAN ARE REFERENCED TO THE NORTH AMERICAN VERTICAL DATUM 1988, NAVD 88. COORDINATES ON THIS PLAN ARE REFERENCED TO THE NORTH AMERICAN VERTICAL DATUM 1983(NAD83 WISCONSIN STATE PLANES, SOUTH ZONE, US FOOT).
- PROJECT CONTROL: SEE CONTROL POINT TABLE ON SHEET 3.
- THE CONTRACTOR SHALL FIELD VERIFY THE FOLLOWING:
- 5.1. ELEVATIONS OF THE BENCHMARKS PRIOR TO COMMENCING WORK, 5.2. PAVEMENT & UTILITY ELEVATIONS WHERE MATCHING INTO EXISTING WORK,
- 5.3. HORIZONTAL CONTROL BY REFERENCING SHOWN DIMENSIONS TO KNOWN PROPERTY LINES. NOTIFY THE ENGINEER OF ANY DISCREPANCIES IN EITHER VERTICAL OR HORIZONTAL CONTROL PRIOR TO PROCEEDING WITH WORK
- CONTRACTOR SHALL PROTECT AND MAINTAIN BENCHMARKS AND SURVEY CONTROL POINTS FROM DISTURBANCE DURING CONSTRUCTION.
- CONTRACTOR SHALL PROTECT EXISTING SITE IMPROVEMENTS TO REMAIN FROM DAMAGE DURING CONSTRUCTION. COST TO RESTORE DAMAGED IMPROVEMENTS TO THEIR ORIGINAL CONDITION, AS ACCEPTABLE BY THE OWNER, WILL BE THE RESPONSIBILITY OF THE CONTRACTOR.
- CONTRACTOR SHALL MINIMIZE INTERFERENCE WITH ADJOINING ROADS, STREETS, WALKS, AND OTHER ADJACENT OCCUPIED OR USED FACILITIES DURING CONSTRUCTION OPERATIONS. DO NOT CLOSE OR OBSTRUCT STREETS, WALKS, DRIVEWAYS, OR OTHER ADJACENT OCCUPIED OR USED FACILITIES WITHOUT PERMISSION FROM OWNER AND AUTHORITIES HAVING JURISDICTION. PROVIDE ALTERNATE ROUTES AROUND CLOSED OR OBSTRUCTED TRAFFIC WAYS IF REQUIRED BY OWNER OR AUTHORITIES HAVING JURISDICTION.

UTILITY CONTACTS

AGENCY CONTACTS

ALWAYS CALL BEFORE YOU DIG CALL 811 OR (800) 242-8511 (262) 432-7910 (877) 500-9592 EMERGENCY ONLY



DF, CP, BL BW BW DRAWN DESIGNED CHECKED BW 8/24/17 15-04-13 APPROVED DATE PROJECT DATE REVISION DESCRIPTION


MONTEREY DAM REMOVAL CITY OF JANESVILLE JANESVILLE, WI





Madison, WI 53703 608.441.0342


GENERAL NOTES


SHEET 2 of 12


























TYPICAL DETAIL SILT FENCE

SILT FENCE NOTES

1.THE SILT FENCE FABRIC SHALL BE PURCHASED IN A CONTINUOUS ROLL CUT TO THE LENGTH OF THE BARRIER TO AVOID USE OF JOINTS. WHEN JOINTS ARE NECESSARY, FILTER CLOTH SHALL BE SPLICED TOGETHER ONLY AT A SUPPORT POST, WITH A MINIMUM 6 INCH OVERLAP, AND BOTH ENDS SECURELY FASTENED TO THE POST. ALTERNATIVELY, OVERLAP AND INTERLOCK TWO POSTS WITH ATTACHED FABRIC AS APPROVED BY THE OWNER'S REPRESENTATIVE.


2.THE SILT FENCE IS TO BE INSTALLED AT LOCATIONS SHOWN IN THESE DRAWINGS ALONG THE DOWNHILL PERIMETER OF DISTURBED AREAS. THE FENCE POST SHALL BE SPACED A MAXIMUM OF 6 FEET APART AND DRIVEN SECURELY INTO THE GROUND A MINIMUM OF 24 INCHES APART.

NOT TO SCALE 3. THE SILT FENCE FABRIC SHALL HAVE A MINIMUM VERTICAL BURIAL OF 6 INCHES. ALL EXCAVATED MATERIAL FROM SILT FENCE INSTALLATION SHALL BE BACK-FILLED AND

COMPACTED ALONG THE ENTIRE DISTURBED AREA.

4. STANDARD OR HEAVY DUTY SILT FENCE SHALL HAVE MANUFACTURED STITCHED LOOPS FOR 2 INCHES X 2 INCHES POST INSTALLATION.

5. SILT FENCES SHALL BE REMOVED WHEN THEY HAVE SERVED THEIR USEFUL PURPOSE, BUT NOT BEFORE THE UPSLOPE AREA HAS BEEN PERMANENTLY PROTECTED AND STABILIZED, OR AS DIRECTED BY THE OWNER'S REPRESENTATIVE.



TYPICAL DETAIL

NOT TO SCALE

GRAVEL CONSTRUCTION ENTRANCE

DF. CP. BL BW BW DESIGNED CHECKED BW 8/24/17 15-04-13 APPROVED

REVISION DESCRIPTION

DATE

PROJECT

MONTEREY DAM REMOVAL CITY OF JANESVILLE JANESVILLE, WI



301 South Livingston Street, Suite 200 Madison, WI 53703 608.441.0342

TYPICAL DETAILS SHEET 4 OF 4

SHEET **12** OF **12**